### MONTANA DEPARTMENT OF FISH AND GAME

POWDER RIVER AQUATIC ECOLOGY PROJECT

ANNUAL REPORT

October 1, 1975 - June 30, 1976

Prepared for:
Utah International, Inc.

By:

Bruce J. Rehwinkel

Mark Gorges

Jerry Wells

THE REAL PROPERTY OF THE MET WINE

The state of the s

tring of proper risks, the

No. of the last of

-it, ignored a more

Apreno i irij

#### **ACKNOWLEDGMENTS**

I would like to thank Utah International Inc. of San Francisco, California which has provided the entire funding for this project. Verification of the invertebrate identifications was done by Dr. George Roemhild and Mr. Richard Oswald, both of Montana State University, Bozeman, Montana. Mr. Oswald also identified all of the midges (family Chironomidae) in the samples. I am especially grateful to the helpful ranchers of the Powder River basin who have allowed access to the river across their land.

#### INTRODUCTION

## Geology-Water Chemistry

The geologic formations of a drainage basin greatly affect the chemical nature of the drainage water. The Powder River watershed drains, in part, Precambrian formations of granites and schists. However, the most obvious contribution to the drainage water chemistry is from a thick series of sedementary strata that range in age from Cambrian to present. This sedementary material is made up of limestones, sandstones, shales, silt-stones, gypsum, shale and coal. Erosion of this substrate occurs at a moderate rate.

Appendix Tables 3 and 4 is the result of four contributing water types.

The first is granitic water coming from Clear Creek and carrying large quantities of silica and calcium. The second type is limestone water flowing from high in the Middle Fork of the Powder River and carrying large amounts of calcium, magnesium, carbonate, chlorides and nitrates.

The third water type is from the lower Middle Fork of the Powder River and is best described as a gypsum water. This water holds a great deal of sodium, potassium, and sulfate. The last type is shale water coming mainly from the Little Powder River. This water carries large amounts of sodium, potassium and sulfate (Swenson, 1953). The resultant water in the main stem of the Powder River has been described as a sodium, bicarbonate, sulfate water (Clark Judy, personal communication.).

Table 1. Physical and chemical parameters of the Powder River at Moorhead.\*

Date	3	Discharge (m <sup>3</sup> /min)	ALK as Specific CaCo <sub>3</sub> Conductance (mg/l) (µmhos/cm)	Dissolved Oxygen Turbidity (ppm) (JTU)	рН
Oct.	16	354	241 2250	10.0 390	7.9
Nov.	19	371	241 1980	12.9	8.4
Dec.	17	193	274 2150	12.8	8.6
Jan.	21	354	299 2180	8.5	8.1
Feb.	19	720	199 1750	11.7	8.1
Mar.	17	1290	241 2500	11.7	8.2
Apr.	29	959	189 1720	10.5 440	8.2

<sup>\*</sup> Data from U.S.G.S.

Table 2. Physical and chemical parameters of the Powder River at Locate.\*

Date	Discharge (m <sup>3</sup> /min)	ALK as CaCo <sub>3</sub> (mg/I)	Specific Conductance (µmhos/cm)	Dissolved Oxygen (ppm)	Turbidity (JTU)	рН
Oct. 22	445	221	2180	12.4	5800	8.3
Nov. 19	588	236	1700	12.4	200	8.5
Dec. 17	1276	283	2400	12.5	140	8.1
<b>Jan. 2</b> 9	<b>3</b> 83	320	2340	7.1	40	7.8
Feb. 28	840	177	1380	12.4	130	8.0
Mar. 17	924	219	2030	12.8	120	8.2
Apr. 29	914	216	2000	10.8	720	8.3
May 18	2016		1090	8.4		8.4

<sup>\*</sup> Data from U.S.G.S.

#### Climate

The climate of the Powder River drainage is characterized as semi-arid in the non-mountainous portion. Much of the area's precipitation (78 %) occurs between April and October with most of the drainage averaging less than 15 inches per year. The yearly discharge of the Powder River (Figure 1) is commonly bi-modal with a smaller March peak followed by the large June run-off and then tapering off to minimal flows for the rest of the year.

The air temperatures of this area vary from -36° to 40°C. with the hot summer temperatures causing rapid evaporative losses. This no doubt impacts the adjacent prairie and is in part responsible for the somewhat sparse vegetation and the resultant erosion. The daily mean water temperatures of the Powder River from April through mid-June 1976 are shown in Appendix Table 5.

### River-Habitat

The river habitat is typical of a prairie stream. The Powder River is silt laden and subject to eratic fluctuations in flow with much of its substrate constantly shifting as bed load. The river develops only shallow pools and lacks aquatic vegetation. The extreme turbidity of the Powder River severely reduces primary productivity due to lack of light penetration resulting in low numbers of aquatic invertebrates.

A map of the study area is shown in Figure 3. The river gradient and area land marks are shown in Figure 4.

# Scope of the Study

The Powder River provides water for man and his livestock and for irrigating croplands. Energy development in the Fort Union area has created a new potential demand for Powder River water. The lack of information concerning the aquatic resource of the Powder River coupled with this




Figure 1. Summary of monthly mean discharges on the Powder River at Moorhead and Locate.




Figure 2. Powder River temperature at Section 1 near confluence with Yellowstone River.




Figure 3. Map of the Powder River showing sampling sites.




Figure 4. Longitudinal profile of Powder River.

potential new demand for its water created the need for this study which is financed by Utah International Inc.

The objective of the study is to collect baseline data of the Powder River to determine the effects of an impoundment and largescale water withdrawals.

This report includes an inventory of fish populations and distribution, aquatic invertebrate distribution and relative abundance, and selected physical and chemical characteristics of the Powder River.

# Description of Sampling Sites

Permanent fish sampling sections have been established as follows:

Section Number	Location
1 1007 1300	Above Interstate Bridge to Burlington Northern Bridge near confluence with the Yellowstone River
2	Near Locate on the A. Young ranch
-	As Minnel on the C. Relean money
. <b>3.</b> 1 U.S. (220)   SAIF W.	At Mizpah on the C. Balsam ranch
<b>3</b> T	Mizpah Creek on the Scott ranch
31	Mizpan creek on the best ranen
4	At Powderville on the Preston ranch
	el le 1,5. Stat el estima lla della della dilipada per lla per seguina el el
5	At Broadus on the Perry ranch
	tilitat dy estrikisen gostifi sedaktyv pris dest
5T	Little Powder River on the Turnbough ranch
6	At Moorhead on the G. Fulton ranch
7	At the Wyoming line on the L. Sams ranch.
/	At the myoming line on the b. bams ranen.

Permanent invertebrate sampling sites have been established as follows:

CASA	ion Number	Location
Stat	ton Number	Location
	1	Above Interstate Bridge, above confluence with the Yellowstone River
	2	Downstream from Locate
	3	At Mizpah Bridge
	3.1.	Mizpah Creek at the bridge
	4	At Powderville Bridge
	5	At Broadus Bridge

Little Powder River on the Turnbough ranch
Moorhead Bridge

5T

#### METHODS AND MATERIALS

River temperatures were monitored with Taylor 30-day recording thermographs. Dissolved oxygen concentrations were measured with a Yellow Springs Instrument Co. oxygen meter and conductivities were measured with a Yellow Springs Instrument Co. conductivity and salinity meter. An Owens-Corning pH meter was used to record pH in situ. Alkalinities are being determined potentiometrically. Turbidity data is from the U.S.G.S.

Macroinvertebrates were collected with a Water's Round square foot sampler, a Needham kick screen and an adult net. Samples were preserved in 10 percent formalin and washed through a U.S. series 30 mesh screen.

Invertebrates were separated from debris and stored in 75 percent isopropyl alcohol.

Fish were collected with the aid of pulsed D.C. electrofishing equipment, drifted 3-inch bar-mesh gill nets and a 50 foot 1/4-inch bag seine. Sport fish were weighed, measured, and tagged prior to release.

#### RESULTS

### Fall Fish Sampling

During the fall of 1975 all seven of the original study sections were sampled. This information was gathered to show the relative abundance of the resident fish populations. A total of 18 species of fish were collected, with the flathead chub (Hypopsis gracilis) the dominant species in each section (Table 6). Section 2 (Locate) showed the greatest number of species (14), while Section 3 showed the fewest (1).

The species composition of the samples show only rare occurrences of

Table 6. Species composition in each of the Powder River sample areas, Fall, 1975.

1-4	u dai?					WEST DE COURT	
Species	7	6	5	4	3	2	1
Flathead	346	965	250	192	108	266	106
chub	87.8%	91.0%	79.6%	81.5%	100%	90.9%	89.2%
Lake chub	11	33	22	19		sline : 1	
	2.8%	3.1%	7.0%	8.0%		0.3%	
Sturgeon	12	28	27	17		5	6
chub	3.0%	2.6%	8.6%	7.2%	W Re-	1.7%	5.1%
Goldeye	14	10				2	3 7 7
	3.5%	0.9%				0.7%	2.5%
River	5	3	2	1		2	1
carpsucker	1.3%	0.3%	0.6%	0.4%		0.7%	0.8%
Shorthead	3	7					
redhorse	0.8%	0.7%					0.8%
Stonecat	2					1	
	0.5%				Will 114 Tru	0.3%	
Carp	1 1 1	4	Tr # (-1)				d V modšaby
	0.3%	0.4%	0.3%		uhi ligitagi		Panigheet
Longnose dace		3	9	2		2	
		0.3%	2.9%	0.8%		0.7%	
Channel		1	3	5		7 1	1 1 2
catfish		0.1%	1.0%	2.1%		2.5%	0.8%
Sauger		1				,	
		0.1%				, The same of the	-1-1-1
Burbot						120	
						0.3%	0.8%
Brassy minnow						1	
						0.3%	
Green sunfish					91	1	
						0.3%	
Sand shiner		5					
		0.5%					
Plains minnow						1	
						0.3%	
Silvery minnow	auto v 13 i					1	
						0.3%	
Creek chub		7	100			2	
	70.4	1000	711	27/	100	0.7%	119
Total	394	1060	314	236	108	293	119

game fish. Length information was taken and is presented in Table 7. Weight information is not included since most fish were small.

Length frequency distributions were compared for the flathead chub in two sections (1 and 7). These two areas showed close agreement with three definite modes occurring. The first mode was between 25 mm and 56 mm, the second between 56 mm and 97 mm and the third occurring between 91 mm and 122 mm. These modes closely agree with age groups zero, one and two according to Brown (1971). The scale method of aging flathead chubs was attempted but annuli could not be detected.

Fall 1975 sampling showed that high turbidities and low water temperatures made electrofishing quite impractical therefore most of the sampling was accomplished with a 50 foot 1/4 inch mesh bag seine. Study sections 2 and 6 were ideal for this technique and the fish samples shown in Table 7 reflect this with high diversities. However, section 3 was very difficult to seine successfully and the fish samples were all of one species; flathead chubs. This may be the only species present in this section but could reflect an inefficient sampling technique.

Future work on resident fish populations will include a varied technique approach to assure the most representative samples.

## Spring Fish Sampling

On April 5, 1976 field work begun to determine the species composition and magnitude of game fish migrations into the Powder River from the Yellowstone River. Fish were captured using pulsed D.C. electrofishing gear, floating gill nets and seines. Captured game fish were measured, weighed and affixed with individually numbered tags. In an effort to tag as many migrating game fish as possible, section 1 (near the confluence with the

Table 7. Fish length (mean and range in mm) by species and study sections, Powder River, 1975.

Species	7	9	2	4	3	2	1
Flathead chub	73.66 ( 20-160)	80 (41-178)		alabera See 5		73 (23-259)	
Lake chub	67 ( 41-99)	72 (38-132)	74 (46-112)	69 (48-89)		104	1 me
Sturgeon chub	74 (41-79)	71 (66-76)	74 (38-89)	70 (43-79)		58 (28-79)	
Goldeye	301 (284-325)	301 (287-343)				303 (295-312)	86 971-102)
River carpsucker	110 ( 38-216)	68 (36-124)	42 (38-46)	28		30 (28-33)	26
Shorthead redhorse	218 (135-264)	285 (201-345)					224
Stonecat	94 ( 89-99)					180	
Carp	462	97 (81–122)	81				
Longnose dace		74 (66-81)	69 (56-79)	67 (64-71)		58 (53-64)	
Channel cat		28	49 (46-53)	54 (43-64)		58 (51-64)	99
Sauger		523				SMIX IIS	
Burbot	=70 4.7**					490	305
Bassy minnow Green sunfish						124	

Yellowstone River) was intensively sampled. Sections 2-8 were also sampled to monitor upstream movement of tagged and untagged game fish.

Prior to this study the importance of Yellowstone River game fish movements into the Powder River had not been assessed in terms of the potential or realized fishery of the Powder River or to the reproduction of Yellowstone River game fish.

#### Sauger

Sauger (Stizostedion canadense) are native to Montana and are one of the most important game fish of the lower Yellowstone River. From April 5 to May 18, 178 sauger averaging 381mm in length and 464 grams in weight were captured, affixed with individually numbered Floy tags and released. These fish were first captured in early April when stream temperature was mainly on the rise (Figure 2) and flow was increasing. Actual flow data will not be compiled by the U.S.G.S. until late 1976. The majority of these fish were captured by electrofishing although extreme turbidities (exceeding 3500 JTU) decreased efficiency of the technique.

The captured sauger were presumably on a spawning migration as indicated by their age structure (Table 8) and gonadal development, with ripe males representing over 95 percent of the captured fish. The period of capture (April 5 - May 18) corresponds to the spawning period of sauger in the lower Yellowstone River as reported by Peterman and Haddix (1975).

Scale samples from 113 sauger captured in the Powder River during the spring of 1976 were used for age and growth determination (Table 8).

Captured sauger ranged from 230-535 mm and represented age classes II-VIII.

Age IV sauger were the most commonly captured year class followed by ages V and III.

It should be emphasized that Table 8 does not represent the age and growth of a discrete population of sanger but rather of a grouping of

Table 8. Sauger age-growth from spring sample 1976.

= 4241					* ,,				
1 Growth								453	
Average Annual Growth (mm)	12.0	12.0	39.40	58.30	6.10	4.10			
Mean Length (mm)	305.5	317.5 (12.5)	356.9 (14.0)	415.2 (16.3)	421.3 (16.6)	425.4 (16.8)	478.0	151 - 151 -	
Length Range (mm)	282-322	230-387	300-402	359-473	349-498	373-500	421-535		
Number oup of Fish	4 4 4 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	20	45	22	15	S	2	113	
Age Group	II	III	IV	>	VI	VII	VIII		

sexually mature sauger, mostly males, from various habitats of the lower Yellowstone River. The growth rates of sauger captured in the Powder River are roughly similar to those reported in the lower Yellowstone (Peterman and Haddix, 1975).

Of the 178 sauger captured and tagged, 174 were captured in Section 1, one in Section 2 and 3 in Section 8. If the 3 sauger captured in Section 8 are Yellowstone River fish, they migrated over 324 km up the Powder River to a point above the proposed construction of the Moorhead dam.

The relatively few fish tagged (178) compared with the length of the river sampled (360 km) and the apparent minimal fishing pressure on the Powder River made upstream recaptures of tagged fish improbable. No tagged sauger were recaptured in the Powder River upstream from the point of tagging. However, a sauger was recaptured in the Tongue River, a tributary which enters the Yellowstone River 57.0 km upstream from the mouth of the Powder River. Another sauger, tagged in Section 1 of the Powder River was recaptured in the Yellowstone River near the mouth of Sand Creek (371 km) upstream from the mouth of the Powder. Another sauger was recaptured in Section 1 of the Powder on May 4 which had been released in the Yellowstone River at Miles City on April 21, 1976, a movement of 55 km in 13 days.

# Channel Catfish

Classified as a game fish by the Montana Legislature in 1975, the channel catfish (Ictalurus punctatus) is a popular sport fish in the lower Yellowstone drainage system. Adult channel catfish are evidently highly migratory and may ascend tributary streams to spawn (Trautman 1957).

Fishermen interviews indicated that channel catfish provided the major contribution to the Powder River sport fishery and suggested that Yellowstone River channel catfish migrating up the Powder River may provide this fishery since catfish are only caught in the late spring and early summer. Channel catfish are caught seasonally by fishermen as far upstream as Arvada, Wyoming (Fred Dabny, personal communication), 434 km upstream from the mouth of the Powder River.

From April 5 to May 21, 95 channel catfish averaging 614 mm in length and 2660 gr in weight were captured in the Powder River and its tributaries using pulsed D.C. electrofishing gear, floating gill nets and seines.

These fish were measured, weighed, affixed with an individually numbered plastic tag attached through the dorsal musculature with 0.032 inch diameter stainless steel wire as described by Pelgen and McCammon (1955) and released. Eighty-seven of these fish were captured in Section 1 as they moved up the Powder River and eight were captured in the Little Powder River, a tributary entering the Powder 249 km upriver. Greatest numbers of channel catfish were captured on April 12, when river temperatures were rising and flow was increasing (Figure 2). Stream discharge has been found to be a major factor influencing adult catfish migrations, with seasonal increases in spring expediting migrations (Van Eeckhout 1974).

The left pectoral spines from 30 channel catfish captured in the Powder River were removed and sectioned for age determination according to the methods of Sneed (1950). These catfish represented age classes II-VIII.

Age IX and older catfish made up 90 percent of the sample which further indicates a spawning migration.

Three channel catfish tagged in Section 1 of the Powder River were recaptured upstream by anglers. Two fish were returned from Powderville

(145 km) 32 and 38 days following tagging. The remaining fish was caught at the mouth of the Little Powder River, representing a movement of 249 km in 33 days. These tag returns suggest the Yellowstone River channel catfish do migrate considerable distance upstream in the Powder River system.

Current field work is being directed toward capturing tagged channel catfish upriver from their point of tagging. This work also encompasses three tributary streams, Mizpah Creek (72 km upstream from the mouth), the Little Powder River (249 km upstream from the mouth) and Clear Creek which enters the Powder River in Wyoming approximately 434 km upstream from the mouth of the Powder.

#### Reproduction

No ripe (sex products easily extrudable) channel catfish have been collected in the Powder River. Of six fish taken by fishermen in Section 1 in late April, four were females with ovaries in the later stages of development. In the 1975 fall sampling, young-of-the-year channel catfish were captured in Sections 1, 2, 4, 5, and 6. This is a good indication of successful channel catfish reproduction in the Powder River or its tributaries.

### Shovelnose Sturgeon

Shovelnose sturgeon (Scaphirhynchus platorynchus) are also native to Montana. Shovelnose sturgeon evidently ascend tributary streams of the Yellowstone River to spawn and large concentrations of them have been noted in the Tongue River by McFarland (personal communication). These fish provide a fishery for those fishermen who have learned where and how to catch them.

Migrating shovelnose sturgeon were captured in the Powder River by electrofishing with pulsed D.C. shocking equipment and by drifting 3-inch




Figure 5. Numbers of shovelnose sturgeon per day at Section 1.

bar mesh gill nets. This latter technique is quite efficient for capturing shovelnose. Shovelnose were first captured in Section 1 of the Powder River on April 13 and were still being taken in early June. At the writing of this report, 179 shovelnose sturgeon have been taken. Each fish was measured, weighed and affixed with an individually numbered tag. Several different tags were used in an attempt to find one which will be retained the longest with the least damage to the fish. Tags used include Floy tags placed behind the dorsal fin, plastic tags affixed with stainless steel wire through the base of the dorsal fin and aluminum poultry tags placed around the caudal peduncle. The poultry tags were found to be undesirable by McFarland in June of this year and all sturgeon are now being tagged with the plastic tag affixed through the base of the dorsal fin with stainless steel wire.

The mean length and weight of the sturgeon captured in the Powder River was 761 mm and 2420 g respectively. The daily catch in Section 1 is shown in Figure 5. Greatest numbers of shovelnose were captured on May 10 when mean daily water temperature was 16°C (Appendix Table 3) and flow was apparently increasing.

On May 11 shovelnose were first captured at sampling sections further upriver with 8 being taken in Section 2, 48 km upstream from Section 1.

On May 13, 4 sturgeon were captured in Section 3, 74 km upstream from Section 1. Sampling sections further upriver have so far failed to produce shovelnose. No tagged shovelnose sturgeon were reported caught by fishermen during this period.

One shovelnose captured in Section 1 on June 2 was tagged May 10, 1974 in the Tongue River at Miles City.

Age and growth information was not obtained since previous work suggests that pectoral fin ray sections are of dubious value and other techniques require sacrificing the fish. None of the 179 sturgeon were in a "ripe" condition and hence none were sexed.

## Tributary Fish Sampling

All fish were captured using pulsed D.C. electrofishing equipment.

Chemical and physical data collected are presented in Table 9.

#### Little Powder River

The Little Powder River is a permanent tributary that enters the Powder River 249 km upstream from the confluence with the Yellowstone. Two sampling runs were made on a 762 meter section approximately 8 km upstream. A mark and recapture population estimate was attempted to determine if it was feasible and applicable to the Powder River.

Flathead chubs (Hybopsis gracilis) were not handled due to time limitations. However, they appeared to be the most abundant fish in the stream. The river carpsucker (Carpoides carpio) followed by the shorthead redhorse (Moxostoma macrolepidotum) were the next most abundant fish species (Table 10). The redhorse appeared to be associated with gravel bottoms in areas of riffles while the carpsuckers were found mainly in areas of silted bottoms and still water.

Of the species present, an estimate using Chapmans modification of the Petersen estimator (Ricker 1958) was made for the shorthead redhorse and river carpsucker (Table 11).

Table 9. Chemical and physical data for two tributaries of the Powder River.

Date	Salinity	Temp.	Specific Conductance	Dissolved Oxygen	pН
6/11	1.0/1000	22.8°C	1340 µmhos/cm	9.4 ppm	8.90
6/11	0.8/1000	21.2°C	1180 µmhos/cm	6.5 ppm	8.22
	6/11	6/11 1.0/1000	6/11 1.0/1000 22.8°C	Date Salinity Temp. Conductance 6/11 1.0/1000 22.8°C 1340 μmhos/cm	Date Salinity Temp. Conductance Oxygen  6/11 1.0/1000 22.8 °C 1340 μmhos/cm 9.4 ppm

Table 10. Species and numbers of fish captured in the Little Powder River.

Species	Sample 1	Sample 2
Flathead chub (Hybopsis gracilis)		Andreas Andreas Andreas
River carpsucker (Carpoides carpio)	85	66
Shorthead redhorse (Moxostoma macrolepidotum)	57	49 **
Carp (Cyprinus carpio)	54	18
Goldeye (Hiodon alosoides)	25	13
White sucker (Catostomus commersoni)	9	18
Green sunfish (Lepomis cyanellus)	7 213 27	The graded 3 to state the second
Stonecat (Noturus flavus)	5	<b>5</b>
Channel catfish (Ictalurus punctatus)	3	and records to the first terms to be the

Table 11. Estimated numbers of shorthead redhorse and river carpsuckers in the study section of the Little Powder River.

Species	Population	Estimate	(95	percent	confidence	intervals)
Shorthead redhorse	138 (+ 45)	27 Laudiller	-4 -	di respi		th Fire ve
River carpsucker	360 ( <u>+</u> 152)	3 % Jan 1900				

Considering the success of this work, estimates are planned for the Powder River to quantitatively assess its fish populations during 1976.

Clear Creek, Wyoming

In an attempt to recover tagged migrating game fish, one sampling run was made on this tributary of the Powder River which enters near Arvada, Wyoming. Sampling problems limited the section to approximately 0.45 km. No sauger, channel catfish or sturgeon were collected. The results of this sampling run are given in Table 12.

Table 12. Species, numbers, mean lengths and mean weights of fish captured in Clear Creek.

Species	Number	Mean Length (mm)	Mean Weight (g)
White sucker (Catostomus commersoni)	27	215	116
Flathead chub (Hybopsis gracilis)	14	124	
Shorthead redhorse (Moxostoma macrolepidoti	12 um)	287	221
Longnose sucker (Catostomus catosumus)	3	288	270
Goldeye (Hiodon alosoides)	3	306	180
lockbass  Amblplites rupestris	2	125	35
liver carpsucker (Carpoides carpio)	1 Enter gran	286	250
Carp (Cyprinus carpio)	1	455	1000
Brown trout  Salmo trutta	1	290	200

#### Invertebrates

Data from October, 1975 and March, April and May, 1976 is included herein. Ice conditions from November through mid-March prevented bottom sampling, and June samples have not been analyzed. At each site on each collection data a Needham kick screen was used for one sample and a Water's Round Sampler was used for three samples. At the Mizpah Creek sample site an Ekman dredge sample replaced each of the normal samples in March and April due to low flows. Due to the shifting nature of the Powder River bottom, riffle areas with rocky, stable substrates were deliberately chosen for the Water's samples in an attempt to sample the more stable benthic communities. The Needham kick samples included all apparent habitat types at each sample site.

Table 13 shows the distribution of all invertebrates collected to date.

Of the taxa identified in the Powder River system, only seven have not been reported from the Yellowstone and Tongue Rivers of eastern Montana (Newell 1975); these are the chironomids Dicrotendipes, Polypedilum and Conchapelopia, the dipteran familes Dolichopodidae and Stratiomyidae, and the mayflies Habrophlebia and Coenis. Stratiomyidae and Caenis have been identified from Rosebud Creek in eastern Montana (Gorges, personal communication).

Overall, Trichoptera and Diptera are the most abundant orders in the samples (Table 14); together they comprise more than 50 percent of the organisms collected. Plecoptera is just as abundant as Diptera in the samples from the main river. At the two tributary sites, Diptera and Ephemeroptera together comprise over 75 percent of the organisms collected.

Table 15 shows the individual abundance of most of the identified taxa. Generic determination has not been completed on Chironomidae,

Tipulidae, Elmidae, Perlodidae, and Gomphidae; therefore, they appear

as families on Table 15. Over 60 percent of all the organisms collected were the caddisfly Chematopsyche, the stonefly family Perlodidae, and the dipteran families Simuliidae and Chironomidae. Chematopsyche and Chironomidae were the only organisms found at each collection site. The family Perlodidae was found at each site on the main river. In general, the upper three sites and the tributaries appear to have a more diverse benthic fauna than the sites closer to the mouth. Actual diversity indicies will be computed after one year of sampling has been completed. This should yield a reasonably large total number of individuals and should allow for some expert confirmation on species identification. Very low numbers of invertebrates have been found in our collections. The quantitative presentation will be developed after a year of sampling is completed.

Further sampling will probably expand the known distribution of some of the taxa identified to date and will probably increase the number of known taxa. The later instars and adults of the insects will be collected during summer sampling. This will facilitate species determination.

Table 13. Distribution of aquatic macroinvertebrates in the Powder River drainage.

			1			1		
the first of the trapping	AND THE		10.00	41	Land of Maria	188	PURNA	a pari
Station was sall line and sall line	.d. 1 1200	2	3	3T	4	5	5T	6
Station	10/10 1 = 10 to 10	- 1 - 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	9.18	J.1				
TAXA   SALE HAMES BELLEGISMEN O	er gent	supple to	an da ji	die ter	prigraff.	eme-Eux	an viy	- a/la
Ephemeroptera de la companya sala	amalengii	d . 70	Lagraphy	e Sur ,	o oake	SIN -	a bring	a sex
Ametropus sp.	rid aces			of The second	ONE T	and anima		S. C.
Baetis parvis	C INC.	-		HARDINA DI PENGA	idelle a		100000000000000000000000000000000000000	AND ARREST OF ACTION
Caenis sp.	- Victoria	V 15 100	14 Film	MARKET SIGNA	Jram s	16 (6)	BAR WATER	TANKE THE CENTRE IN THE
Epeorus sp.				73.0		and in the later		Total Services
Habrophlebia sp.	Lunas e	102	The Liverie	The state of the s	THE REAL PROPERTY.	Lympe	10 150	A STATE OF THE SECOND
Leptophlebia sp.	2 wester		100	10	ACCIDENCE OF	1	A THE COL	977
Rhithrogena sp. Stenonema sp.	2- 402-131	(CENTRES	15178		and the second	Christian		A CARA TOTAL
Tricorythodes minutus	india.	U SEEV	and E	EF BE	and the	LIBNE-	13 (114)	THE PARTY OF THE PARTY.
							11 17	
Trichoptera = 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	a tri gyb	Ed Tipo	5 aut	- Igola	es Lina	CONT.	- Iraumi	50.30
Brachycentrus sp.								AND THE PROPERTY OF
Chematopsyche sp.	THE PERSON NAMED IN COMM	NAME OF REAL PROPERTY.		TOTAL PROPERTY			Commonwealth.	SALES OF CHILDREN PART
Hydropsyche sp.		TO SELECT OF SELECT	NOTE OF STREET		AND CHARLES	4	The state of the s	
Polycentropus sp.	Maria Cara	E DURIT	201000000	GENERAL SERVICE	AN BIER	WIE ZES	The state of the s	
Diptera William and and property	al /Li	data d	law her	S FEE	Bell 1	Drawn .	Espender v	14 4-1
		0.00	1	4.				
Ceratopogonidae	T 177287	in sells	T The	THE PROPERTY OF	4 3	Yeste	ord I'm	784E-1
Chironomidae	HOW STREET	The state of the s	PORTE TO THE	THE PROPERTY OF	Marin and	TOPPO THE		A SECULLARIAN DE LA COLONIA
Cryptochironomus	THE PARTY OF THE P				o e fi	0.000	The surround	
Dicrotendipes Paralauterborniella					1 2 P		PARTICIONE I	
Polypedilum						11		182 11
Rheotanytarsus Group					10		AND THE PARTY OF T	
Conchapelopia					- 1		BE ALLED	ESPECIAL CONTROL CONTROL
Cardiocladius		Service 177*	Telling to This		207.02° 7.77	ALC: SEPTEMBER		
Orthocladius						76	THE PROPERTY OF THE PARTY OF TH	CONTRACTOR ACTOR CORN
Dolichopodidae	W N			BBALTIES		Salt This	The same	
Empedidae		15	THE HELLING	1	SELECT PROPERTY	PUNCHER C	AR WES	
Simuliidae Simulium			1	100 CO 200 TO NO.	1			
Stratiomyidae	The state of			- Charles in the		I SAMPLE TO	E TOTAL AND ALLES	2007/01/10/19
Tipulidae*			Section of the Park				MONTH TOTAL	
Dicranota				CONTRACTOR OF	1		1 7 10	Annual Control of Control
Plecoptera								
Acroneuria					Met. rate nine		1	
Brachyptera	Mar and	EMPONE IN LIGHT	TO THE PERSON	1	**************************************	ATTECH COMPANY	R	
Perlodidae*	and the second of the second	e proposorano	-/	1	2005 1000			DESCRIPTION OF THE PARTY
	T	A CONTRACTOR OF THE PARTY OF TH		1		UI PERMIT	3	

Table 13 Continued.

	1	ı la		80	1		A BILLIOSA (2	2 11
Station	1	2	3	3T	4	5	5T -	6
TAXA		la la		1				
<b>O</b> donata			16					
Argia Gomphidae* Gomphus	S TO S THE STREET	187						\$1.00 mg/s
Colcoptera		200	W 81					Leften Ligger
Elmidae (adults) Dubiraphia Microcylloepus Stenelmis		VI X 1 2	# 152 = 012		a second			
Hemiptera		.55			4 2%	ter.		
Ambrysus mormon	ta Tyaci							VanTen-
Annelida Oligochaeta*		x 5		U ARREST TO CO				
Mollusca Pelecypoda*	, †M =	y 180	11:				2005597282898	
Malacostraca Amphipoda*			= =	THE TRACE	X = 0			

<sup>\*</sup> Organisms not identified to lower taxa due to their size or condition.

All identifications are tentative.

Table 14. Number of organisms in each Order and their percent\* composition, in parentheses, for all collections at each site. Dashes indicate zero counts.

Station	1	2	3	3T	4	5	5Т	6
Order_				- 5		]r		* * * * * * * * * * * * * * * * * * *
Ephermeroptera	u Kemese en e	3 (5)	3 (5)	129 (52)	9 (3)	4 (6)	78 (22)	37 (13)
Trichoptera	122 (74)	31 (51)	5 (9)	12 (5)	222 (66)	2 (3)	25 (7)	64 (22)
Diptera	9 (5)	3 (5)	9 (16)	96 (39)	83 (25)	13 (19)	194 (54)	90 (31)
Plecoptera	30 (18)	19 (31)	40 (70)	-	18 (5)	11 (16)		55 (19)
Odonata	3 (2)	<u> </u>	-	3 (1)	1 (>1)	2 (3)	1 (>1)	1 (>1)
Coleoptera	-	8 <del>7</del>		-	2 (1)		50 (14)	40 (14)
Hemiptera	e di	(1) (1)		-			1 (>1)	nik ose-jengaji
Others	#1 * - " <u>* 1</u>	5 (8)	- 3	7 (3)		35 (52)	7 (2)	1 (>1)

<sup>\*</sup> Rounded to the nearest whole number.

Table 15. Numbers and percent composition (in parentheses), rounded to the nearest whole number, of all benthic organisms collected.

STATION	1	2	3	<b>3</b> T	4	5	5T	6
Number of Samples	12	16	16	. 12	16	12	8	16
TAXA								el J
Ephemeroptera								
Ametropus	- 1-	3	3		9 F	2	1.05	ha de xwi
Baetis	- W-	(5) -	(5)	1	a 87 <u>-</u>	(3)	4	2
Caenis		(H)	_	(>1) 125			(1) 6	(1)
Epeorus	a = = <del>-</del>	-	-	(51)	9 DB - 4	2	(2)	9
Habrophlebia	T= 3	-	-		1	(3)		(3) 11
Leptophlebia			- III	3	( <b>&gt;</b> 1)	72.1 ·	52	(4)
Rhithrogena	· -	17-	_	(1)	(1) 6	_	(15)	(1)
Stenonema	+ ,	-	* -	124	(2)	24	16	(1) 1
Tricorythodes	- V - M		-	_	a. <u>  x</u>		(4)	( <b>&gt;</b> 1)
<b>Fricho</b> ptera				13				(3)
Brachycentrus	12 =	199		_				11
Chematopsyche	122	31	5	12	220	2	21	(4) 30
Hydropsyche	(74)	(51)	(9)	(5)	(66) 2	(3)	(6) 2	(10) 23
Polycentropus	18 J. P. P. A.	413		. HW	(1)		(1) 2	(8)
iptera							(1)	
Ceratopogonidae Chironomidae	1 (1) 7	-	1 (2) 6	3 (1)	-			•
Dolichopodidae	(4)	(5)	(11)	53 (21) 2	19 (6)	9 (13) 2	30 (8)	20 (7)
Empedidae	1	-	1	(1)	3	(3)	2	17
Simuliidae	(1)	-	(2)	<b>3</b> 3	(1) 61	(1) 1	(1) 158	(6) 52
Stratiomyidae	-	€		(13)	(18)	(1)	(40) -	(18)
Tipulidac	= - ar		1 (2) -29	(>1) 4 (2)		- 1	4 (1)	1 ( 1)

Table 15. Continued

STATION	1	2	3	<b>3</b> T	4	5	5T	6	
Number of Samples	12	16	16	12	16	12	8	16	
TAXA		1 181	8 I	SUS =		973		Tanga 15	if life.eK
Plecoptera									
Acroneuria Brachyptera	6 (4)	1 (2)	1 (2)	1477 <b>-</b>	5 (1)	-1		2 (1) 3	
Perlodidae	24 (15)	18 (30)	39 (68)	# = <u>V</u>	13 (4)	(1) 10 (15)	- 1-	(1) 50 (17)	
<b>O</b> donata	21 21 3	, Wi	723		2 1			** - 17 A.5*-30	
<b>A</b> rgia	100	<del></del>	- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1-	2 (1)	1 (>1)	in-		réarga	
Gomphidae	3 (2)	£ -	- 0	( <b>&gt;</b> 1)		2 (3)	1 (>1)	1 (>1)	
Coleoptera									
Elmidae	- ·	122	-		2 (1)	10-	50 (14)	40 (14)	
Hemiptera								= nitration	
Ambrysus	ji 12-	2 -	-	-	-	-	1 (>1)		
Others	-	5 (8)	: -	7 (3)	_	35 (52)	7 (2)	1 (>1)	
Total Number of Organisms	164	61	57	247	335	67	356	288	
Average Number Per Sample	13.7	3.8	3.6	20.6	20.9	5.6	44.5	18.0	




Table 3.

MOORHEAD

Dis Al	Cn			1	(1)				
	(mg/1)	Fe (mg/1)	Fe (mg/1)	Boron (mg/1)	(mg/1)	Cu (mg/1)	Hardness (mg/1)	Ca (mg/1)	Mg (mg/1)
	30	20,000	20	340	5.1	E.	350	130	65
10	40	15,000	0	770	14	2	310	130	55
		1	10	250	3.6		360	150	64
<u></u>	10	2,100	0	320	9.9	(E)	270	130	59
		1	30	250		0	220	100	42
			10	310	9.3		330	140	54
in y	40	30,000	20	70	13		260	66	48
	# F								
K (mg/1)	CL (mg/1)	SO <sub>4</sub> (mg/1)	Dissolved Silica SiO <sub>2</sub> (mg/l)	Hardness Ca-Mg	CO <sub>2</sub>	BOD	Bicarb HCO <sub>3</sub> (mg/1)	Total P (mg/l)	
17	180	750	5.1	590	5.9	1.5	294	.39	
6.1	170	009	6.8	550	1.9	1.2	294	.01	
5.7	150	009	8.8	640	1.3	0.4	334	00.	
6.9	200	290	10	570	4.6	2.4	365	.03	
6.3	150	480	7.5	420	3.1		243	.07	
6.5	220	700	9.9	570	3.0		294	.30	
5.0	92	520	5.8	440	2.3		231	.68	

\* Provisional Data from U.S.G.S.

	4
le	_
Lab	ab

	,										
. (	ı			7 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1			1.9				May 18
	263	2.1	510	6.4	810	66	1:1	6.7	290	50	Apr. 29
	267	2.7	520	7.3	069	110	.15	8.9	270	53	Mar. 17
	216	3.5	340	9.9	400	100	.14	8.4	180	34	Feb. 28
	390	6.6	009	10.0	099	190	.08	7.4	310	61	Jan. 29
	345	4.4	069	& &	710	160	.17	6.9	260	71	Dec. 17
	288	1.5	520	6.5	009	110	.51	6.1	210	54	Nov. 19
	270	2.2	470	5.8	029	140	.72	7.1	290	53	Oct. 22
v. 30	Bicarb HO <sub>3</sub> (mg/1)	s CO <sub>2</sub> (mg/1)	Hardness Ca-Mg	Dis SiO <sub>2</sub> (mg/1)	SO <sub>4</sub> (mg/1)	Ce (mg/1)	Total P (mg/l)	Dis. K (mg/1)	Dis. Na (mg/1)	Dis Mg (mg/1)	Date
			34.0			1 200		1			May 18
	120	290	16.0		10	55,000	9	70			Apr. 29
	120	300	5.7		1	1					Mar. 17
	80	160	7.5								Feb. 28
	140	280	9.9		20	2,200	2	10			Jan. 29
	160	410	5.8				i,				Dec. 17
	120	290	5.1			De i					Nov. 19
	100	250	3.4		20	28,000	7	50			Oct. 22
	Ca (mg/1)	Hardness (mg/1)	(mg/1)	Boron (mg/1)	Fe (mg/1)	Fe (mg/1)	1)		Dis.	A1 (mg/1)	
	Dis.	Non-Carb	Nitrate	Dis.	Dis.	Total	Dis.	Total		Total	

Table 5. Daily Mean Temperature <sup>O</sup>C Powder River.

Date	Interstate	Powderville	Moorhead
April 1			
2 3		194	
3		11.7	
4		12.2	
× 5		211.1	12.8
5 6		12.5	11.7
7	12.2	13.9	11.9
8	11.9	14.4	12.2
9	12.2	14.4	13.0
10		13.6	11.1
11		10.6	12.8
12		10.3	14.2
13	15.6	10.0	15.6
14	13.6	10.0	13.6
15	12.8	10.6	13.6
16	11.9	10.8	9.7
17	7.8	10.0	8.3
18	6.7		10.3
19	7.5	- 1	10.3
20	8.0		10.0
21	9.4		11.1
22	8.9	11.1	10.6
23	9.4	11.1	11.1
24	8.6	10.3	12.2
25	9.2		12.2
26		10.6	
27	9.7	10.0	10.0
28	7.5	10.6	5.8
29	6.4	6.4	5.6
30	6.1	7.2	6.9
	6.9	9.7	10.0
1	8.3	13.0	12.5
2	9.7	12.8	12.8
3	10.0	13.3	13.6
4	11.1	15.0	15.0
5	11.9	15.3	14.7
6	11.7	15.8	13.9
7	12.2	15.8	14.2
8	13.6	16.9	16.6
9	14.2	18.0	16.9
10	16.1	18.3	17.8
11	16.1	18.9	16.7
12	13.1	14.7	13.0
13	10.8	14.4	13.3
14	14.2	No record	16.3
15	14.4		14.4
16	13.9		13.9
17	15.6		15.6
18	16.6		18.0
19	16.1		19.2
20	17.2		19.2

Table 5. Continued

Date		Interstate	Powderville	Moorhead	<u> </u>
May	21	17.5	No record	18.0	
,	22	16.4	*	16.9	
	23	17.2		14.7	
	24	15.0		13.6	
	25	14.7		16.9	
	26	13.3		15.6	
	27	15.3		16.9	
	28	17.8		19.4	
- 33	29	17.0		18.3	
	30			18.3	
	31			19.2	
June	1			20.3	
June	2			20.0	
	3			20.0	
	4			20.8	
	5	20.6		17.5	
		21.1		17.8	
	6 7	19.4		21.7	
		20.3		21.9	
	8			22.5	
	9	20.3		22.2	
	10	20.8			
	11	21.4			
580	12	21.4			
	13	18.6			
	14	15.8			
	15	15.0			100, 2
	16				
	17				V
	18				
	19		1 1990		
	20	2 5 5 6 6			
	21				
	22				A1
	23				

#### LITERATURE CITED

- Brown, C.J.D. 1971. Fishes of Montana. Big Sky Books, Montana State University, Bozeman, MT.
- Newell, R.L. 1975. Investigation of Aquatic Communities, Old West Regional Commission Annual Report, July 1, 1974-June 30, 1975.
- Pelgen, D.E., G.W. McCammon 1955. Second progress report on the tagging of white catfish (*Ictalurus catus*) in the Sacramento San Joaquin Delta. Calif. Fish and Game. 41(4):261-269.
- Peterman, L.G. and M.H. Haddix 1975. Lower Yellowstone Fishery Study, Progress Report No. 1. Montana Dept. of Fish and Game, Miles City, MT.
- Ricker, W.E. 1958. Handbook of Computations for Biological Statistics of Fish Populations. Fisheries Research Board of Canada Bulletin No. 119.
- Sneed, K.E. 1950. A method for calculating the growth of channel catfish, Ictalurus lacustris punctatus. Trans. Am. Fish. Soc. Vol. 80.
- Swenson, H.A. 1953. Geochemical relationships of water in the Powder River Basin, Wyoming and Montana. Transactions, American Geophysical Union, Vol. 34, No. 3.
- Trautman, M.B. 1957. The fishes of Ohio. Ohio State Univ. Press. 683pp.
- Van Eeckhout, G. 1974. Movement, reproduction and ecological relationships of channel catfish, in the Little Missouri River, N. D. 1972-1973.

  Master's thesis, University of North Dakota.

Waters referred to: Powder River - 21-0750-02

Little Powder River - 21-0550-02

Mizpah Creek - 21-0755-10

#### THE RESERVE OF THE PERSON NAMED IN

- Brown of a city of the Company of th
  - THE AND ASSESSMENT OF THE RESIDENCE OF T
- integral affilia stones exerging industria state manufold with affilia in the last manufold with a first in the companion of the first state in the companion of the first state in the companion of the companion
- The state of the first property of the state of the state
- The factor of the state of the
  - Administration of the composition of the control of
- newill removal Autoria to the Company of the Autoria Sawanda Company of the Autoria Sawanda Company of the Autoria Sawanda Company of the Com
  - and the companies of the street of the contract of the contrac
- Profession C. D. L. Department Teperator for the state of the state of

Carter Control of the Control of the